

**Exhibit 4 Principal Constructed Components of Plan**

<b>Name</b>	<b>Quantity</b>	<b>Estimated cost (2008)</b>
Proposed Pipeline	16,000 feet of 8" PVC pipe (low pressure)	\$290,000
	900 feet of 6" ductile iron pipe	\$32,000
Road crossing	100 feet jacking	\$146,000
Pressure reducing facility	Cast in place vault and pressure reducing valve	\$6,000
<b>Proposed Pipeline Total Estimated Costs:</b>		<b>\$474,000</b>
Alternative Pipeline	4,000 feet of 8" PVC pipe (low pressure)	\$73,000
	700 feet of 6" ductile iron pipe	\$25,000
<b>Alternative Pipeline Total Estimated Costs:</b>		<b>\$98,000</b>