

PRIEST LAKE WATER MANAGEMENT PROJECT OUTLET DAM IMPROVEMENTS





OBLIQUE AERIAL PHOTO

NOT TO SCALE

М	1601 5th Avenue	Client							_			_	Designed	E. Sheesley	Eng check	S. Phillips
M	Suite 800 Seattle, Washington 98101	1DAHO	IDAHO									• \	Drawn	T. Morrison	Coordination	
	Seattle, washington 96101	the state	DEPARTMENT OF WATER RESOURCES 322 Front Street Suite 648								BID)	Dwg check		Approved	
	T +1 (425) 778 6243 W mottmac.com	A THE STORE	P.O. Box 83720 Boise, Idaho 83702							FUR	עום		Scale at AN	SI D Status	Rev	Security
	W motunac.com		P (208) 287-4800													
		AFSOURCE	F (208) 287-6700	0	5/6/20	TM	90% SUBMITTAL	SK SP	Proj	oject Number	B/O 1	Total	Drawing Nur		0 1	
				Rev	Date	Drawn	Description	Ch'k'd App'd	d	376997	I	25		U.	S-1	
aworking/hmm/porte_harhore/tad60807/dme25001/3	76007 - Priest Lake Dam - Cover Sheet dwg, Jun 12, 2	020 - 5:25DM Tadlock Brice														

SHEET INDEX										
SHEET NO.	TITLE									
1	COVER SHEET / INDEX OF DRAWINGS									
2	GENERAL NOTES AND ABBREVIATIONS									
3	GENERAL NOTES									
4	OVERALL SITE PLAN - EXISTING CONDITIONS									
5	PHOTOS SHEET - EXISTING CONDITIONS 1									
6	PHOTOS SHEET - EXISTING CONDITIONS 2									
7	CONSTRUCTION ACCESS AND WORK LIMITS PLAN									
8	CONSTRUCTION PHASING & DEWATERING PLAN 1									
9	CONSTRUCTION PHASING & DEWATERING PLAN 2									
10	DEWATERING DETAILS									
11	TEMPORARY EROSION & SEDIMENT CONTROL DETAILS									
12	GENERAL DAM PLAN AND ELEVATION									
13	OUTLET STRUCTURE SECTIONS AND WORK LIST									
14	TAINTER GATE ELEVATION AND SECTION									
15	TAINTER GATE DETAILS									
16	TRUNNION GREASE TUBE REPLACEMENT DETAILS									
17	MISCELLANEOUS STEEL DETAILS									
18	SUBSTRUCTURE PLAN									
19	APRON EXTENSION SECTIONS									
20	APRON REINFORCING PLAN									
21	APRON WALL ELEVATIONS									
22	APRON REINFORCING SECTIONS									
23	PIER 6 REPAIR DETAILS									
24	MISCELLANEOUS DETAILS 1									
25	MISCELLANEOUS DETAILS 2									

DWG NO. S

CS-1 GN-1

GN-2 GP-1 PH-1

PH-2 C-1

C-2 C-3 C-4 C-5 S-1 S-2

S-3 S-4

S-5 S-6 A-1 A-2 A-3 A-4

A-5 P-1

M-1 M-2

DAM INFORMATION

Dam Name: Priest Lake (Outlet Dam) River: Priest River NID Storage: 76,100 Acre Feet NID Height: 12 feet (8'-6" at Radial Gates) Primary Dam Type: Concrete Year Completed: 1978 NID Harzard Potential: Significant

> Priest Lake Water Management Project Outlet Dam Improvements

COVER SHEET / INDEX OF DRAWINGS

GENERAL NOTES

SCOPE OF WORK:

- WORK DETAILED ON THE DRAWINGS AND APPLICABLE ITEMS DESCRIBED IN THE GENERAL STRUCTURAL NOTES AND SPECIFICATIONS.
- DRAWINGS TO BE READ IN CONJUNCTION WITH SPECIFICATIONS AND ALL OTHER DRAWINGS RELATED TO THE PERFORMANCE OF THIS WORK THE CONTRACTOR IS RESPONSIBLE FOR THE VERIFICATION AND COORDINATION OF ALL SPECIFICATIONS, PLANS, SECTIONS AND DETAILS PRIOR TO PROCEEDING WITH ANY WORK. IMMEDIATELY NOTIFY THE ENGINEER OF RECORD OF ANY DISCREPANCIES FOUND.
- CONTRACTOR SHALL PROVIDE TEMPORARY SHORING, BRACING AND PROTECTION FOR ALL WORK IN PROGRESS UNTIL THE WORK IS COMPLETE
- CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND UTILITIES PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL CONDUCT THEIR OPERATIONS IN
- 5 ACCORDANCE WITH ALL CURRENT LOCAL, STATE, AND FEDERAL CODES COVERING SUCH OPERATIONS. THE CONTRACTOR WILL BE REQUIRED TO COORDINATE THEIR WORK WITH THE IDAHO WATER RESOURCE BOARD (OWNER), BONNER COUNTY, AND OTHER CONTRACTORS, IF ANY,
- THE CONTRACTOR SHALL HAVE AN ENGINEER LICENSED IN THE STATE OF IDAHO PREPARE AND STAMP A SET OF PLANS AND ALL CALCULATIONS FOR THE FOLLOWING WORK

-COFFERDAM DESIGN -STRUCTURAL LIFTING AND TEMPORARY SHORING OF

STRUCTURES -JACKING FRAMES

-DESIGN CHECK OF EXISTING STRUCTURE FOR CONTRACTOR'S OPERATIONS INVOLVING THE USE OF THE EXISTING STRUCTURE -OTHER WORK BY CONTRACTOR ON THESE PLANS NOT MENTIONED

PLANS AND CALCULATIONS SHALL BE SUBMITTED TO THE OWNER'S REPRESENTATIVE FOR REVIEW AND APPROVAL. THE CONTRACTOR SHALL ALLOW AT LEAST TWO WORKING DAYS PER DRAWING AND ONE DAY PER FOUR PAGES OF CALCULATIONS FOR REVIEW A MINIMUM OF TEN WORKING DAYS MUST BE ALLOWED FOR EACH SET OF DRAWINGS OR CALCULATIONS SUBMITTED FOR REVIEW. NO WORK MAY BEGIN

UNTIL THE RESPECTIVE SUBMITTALS ARE APPROVED. ALL COSTS FOR PREPARING THESE PLANS AND CALCULATIONS SHALL BE INCLUDED IN THE CONTRACTOR'S BID PRICE, INCLUDING RESUBMITTALS. THE CONTRACTOR'S ENGINEER SHALL BE RESPONSIBLE FOR THE STABILITY OF THE STRUCTURE DURING ALL PHASES OF THE REHABILITATION WORK

7. MULTIPLE MOBILIZATIONS MAY BE REQUIRED TO COMPLETE THE

DRAWINGS AND SPECIFICATIONS:

- DO NOT SCALE DRAWINGS FOR DIMENSIONS NOT GIVEN. ADVISE THE OWNER'S REPRESENTATIVE OF DIMENSIONAL
- DISCREPANCIES VERIFY ALL EXISTING FIELD CONDITIONS AND DIMENSIONS PRIOR 3 TO COMMENCING CONSTRUCTION.
- THE CONTRACTOR SHALL PERFORM NO PORTION OF THE WORK AT ANY TIME WITHOUT CONTRACT DOCUMENTS OR WHERE REQUIRED, APPROVED SHOP DRAWINGS, PRODUCT DATA OR SAMPLES FOR SUCH PORTION OF THE WORK.

CONSTRUCTION SAFETY:

THESE DRAWINGS DO NOT INCLUDE PROVISIONS TO SATISFY SAFETY REQUIREMENTS CONTRACTOR IS SOLELY RESPONSIBLE FOR ENSURING SAFETY DURING CONSTRUCTION AND FOR CONFORMANCE TO ALL APPLICABLE OSHA STANDARDS AND OTHER APPLICABLE CODES. JOBSITE VISITS BY THE OWNER'S REPRESENTATIVE SHALL NOT CONSTITUTE APPROVAL AWARENESS OR LIABILITY FOR ANY HAZARDOUS CONDITIONS

BUILDING CODES AND SPECIFICATIONS:

- US ARMY CORPS OF ENGINEERS, DESIGN OF HYDRAULIC STEEL STRUCTURES, ENGINEERING TECHNICAL LETTER (ETL) 1110-2-584, JUNE 2014
- 2. US ARMY CORPS OF ENGINEERS, DESIGN OF SPILLWAY TAINTER GATES, ENGINEERING MANUAL (EM) 1110-2-2702, JANUARY 2000 (SUPERCEDED BY ETL 1110-2-584)
- AMERICAN INSTITUTE OF STEEL CONSTRUCTION, SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS, AISC 360-10, JUNE 2010
- AMERICAN SOCIETY OF CIVIL ENGINEERS, MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES, ASCE 7-10 THIRD PRINTING, MARCH 2013
- AMERICAN CONCRETE INSTITUTE, BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE, ACI 318-14, SEPTEMBER 2014

REHABILITATION NOTES:

- THE CONTRACTOR SHALL EXAMINE AND VERIFY. IN THE FIELD. ALL CONDITIONS AND DIMENSIONS. DIMENSIONS OF THE EXISTING STRUCTURES SHOWN ON THESE PLANS ARE FOR GENERAL REFERENCE ONLY THEY HAVE BEEN TAKEN FROM THE ORIGINAL CONSTRUCTION DRAWINGS AND ARE NOT GUARANTEED. THE CONTRACTOR SHALL TAKE ALL SUCH FIELD MEASUREMENTS AS ARE NECESSARY TO ENSURE PROPER FIT OF THE FINISHED WORK AND THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR THEIR ACCURACY. IF THE FIELD CONDITIONS AND DIMENSIONS DIFFER FROM THOSE SHOWN ON THE PLANS, THE CONTRACTOR SHALL USE THE FIELD CONDITIONS AND DIMENSIONS AND MAKE THE APPROPRIATE CHANGES TO THOSE SHOWN ON THE PLANS, AS APPROVED BY THE OWNER'S REPRESENTATIVE. WHEN SHOP DRAWINGS BASED ON FIELD MEASUREMENTS ARE SUBMITTED FOR APPROVAL, THE FIELD MEASUREMENTS MADE SHALL BE INDICATED ON THE SHOP DRAWINGS SUBMITTED FOR REFERENCE OF THE REVIEWER
- THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE FACT THAT, DUE TO THE CONDITION OF EXISTING STRUCTURES, THE EXACT EXTENT OF WORK CANNOT ALWAYS BE ACCURATELY DETERMINED PRIOR TO THE COMMENCEMENT OF WORK THESE CONTRACT DOCUMENTS HAVE BEEN PREPARED BASED ON FIELD INSPECTION AND OTHER INFORMATION AVAILABLE AT THE TIME. ACTUAL FIELD CONDITIONS MAY REQUIRE MODIFICATIONS TO CONSTRUCTION DETAILS AND WORK QUANTITIES. THE CONTRACTOR SHALL PERFORM THE WORK IN ACCORDANCE WITH FIELD CONDITIONS AS DIRECTED BY THE OWNER'S REPRESENTATIVE.
- THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR ALL DAMAGE TO THE EXISTING STRUCTURE CAUSED BY THEIR OPERATIONS WHICH IS NOT INCLUDED AS PART OF THE INTENDED WORK. ALL DAMAGE TO THE EXISTING STRUCTURE, WHICH IS NOT PART OF THE INTENDED WORK, SHALL BE REPAIRED BY THE CONTRACTOR WITHOUT COST TO THE OWNER, AND TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE.
- LAWN AREAS DISTURBED BY THE CONTRACTOR, AS PART OF WORK TO BE PERFORMED UNDER THIS CONTRACT, SHALL BE RESTORED AS SPECIFIED TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE INCLUDING DISTURBANCE TO STAGING AREAS ALL DISTURBED GRASS AREAS SHALL BE GRADED IN A MANNER APPROVED BY THE OWNER'S REPRESENTATIVE, TOPSOILED, AND SEEDED

REMOVAL, EXCAVATION, AND BACKFILL NOTES:

- 1. THE CONTRACTOR SHALL PROVIDE ALL TEMPORARY SUPPORTS, BRACING, AND OTHER DEVICES REQUIRED OR DIRECTED BY THE OWNER'S REPRESENTATIVE TO PROTECT THE SAFETY OF THE ADJACENT STRUCTURES AND UTILITIES. ALL COSTS FOR THIS WORK SHALL BE INCLUDED IN CONTRACTORS BID.
- 2. DURING REMOVAL OPERATIONS, THE CONTRACTOR SHALL NOT DROP WASTE CONCRETE DEBRIS AND OTHER MATERIAL INTO PRIEST RIVER OR ON TO ADJACENT PROPERTIES EXCEPT WHERE THE PLANS OR SPECIFICATIONS SPECIFICALLY PERMIT DEPOSITION OF MATERIAL. PLATFORMS, NETS, SCREENS, OR OTHER PROTECTIVE DEVICES SHALL BE USED TO CATCH THE MATERIAL. IF THE OWNER'S REPRESENTATIVE DETERMINES THAT ADEQUATE PROTECTIVE DEVICES ARE NOT BEING EMPLOYED, THE WORK SHALL BE SUSPENDED UNTIL ADEQUATE PROTECTION IS PROVIDED. IF MATERIAL FALLS ON THE AREA BELOW AND ADJACENT TO THE DAM, IT SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR IMMEDIATELY.
- 3. THE COST OF FURNISHING, INSTALLING, MAINTAINING, REMOVING, AND DISPOSING OF ALL ACCESS ROADS, PLATFORMS, NETS SCREENS, AND OTHER PROTECTIVE DEVICES, SHALL BE INCLUDED IN THE BID PRICE OF THE CONTRACT.
- 4. CARE SHALL BE TAKEN TO RETAIN NATURAL GROWTH AND PREVENT DAMAGE TO TREES WITHIN AND OUTSIDE THE LIMITS OF CONSTRUCTION, AND NOT SCHEDULED FOR REMOVAL. ANY DAMAGE CAUSED TO THIS NATURAL GROWTH SHALL BE RESTORED AT THE EXPENSE OF THE CONTRACTOR, AS DIRECTED BY THE OWNER'S REPRESENTATIVE
- 5. THE CONTRACTOR SHALL CONDUCT REMOVAL OPERATIONS TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE SO AS NOT TO UNDULY DISTURB UNDERLYING MATERIALS WHICH ARE TO REMAIN IN PLACE. THE CONTRACTOR SHALL PERFORM ALL WORK WITH CARE SO THAT ANY MATERIALS WHICH ARE TO REMAIN IN PLACE, OR WHICH ARE TO REMAIN THE PROPERTY OF THE OWNER WILL NOT BE DISTURBED.

REMOVAL, EXCAVATION, AND BACKFILL NOTES (CONT'D):

6. THE CONTRACTOR SHALL REPAIR OR REPLACE ANY DAMAGE CAUSED BY THE CONTRACTOR'S ACTIVITIES TO ALL ACCESS ROADS TO THE OWNER'S SATISFACTION AND AT NO ADDITIONAL COST TO THE OWNER'S REPRESENTATIVE.

UTILITY NOTES:

- 1. LOCATION OF UTILITIES, PUBLIC AND/OR PRIVATE, INDICATED AS EXISTING AS SHOWN ON THE PLANS, ARE APPROXIMATE ONLY. THEIR EXACT LOCATION SHALL BE DETERMINED IN THE FIELD ADDITIONAL UTILITY LINES WHETHER ABANDONED OR IN SERVICE MAY EXIST AND IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONDUCT OPERATIONS AND TAKE THE NECESSARY PRECAUTIONS TO PREVENT INTERFERENCE WITH OR DAMAGE TO THESE OR OTHER FACILITIES DURING THE COURSE OF CONSTRUCTION.
- SHOULD UTILITIES BE ENCOUNTERED DURING CONSTRUCTION WHICH INTERFERE WITH THE WORK AND FOR WHICH PROVISIONS ARE NOT PROVIDED ON THE PLANS, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER'S REPRESENTATIVE OF THEIR EXISTENCE AND EXTENT OF CONFLICT WITH THE WORK. THE CONTRACTOR SHALL MAKE ARRANGEMENTS WITH THE OWNING AGENCY TO MODIFY ITS FACILITY IN ORDER TO ALLOW THE WORK TO PROGRESS. ANY WORK AS A RESULT OF SUCH UTILITY CONFLICTS WILL BE PERFORMED AT NO ADDITIONAL COST TO THE OWNER.
- ANY DAMAGE, CAUSED BY THE CONTRACTOR'S OPERATIONS, FROM MINOR SCRAPES TO SEVERING OF THE UTILITY SERVICE, SHALL BE IMMEDIATELY REPORTED TO THE UTILITY OWNER AND THE OWNER'S REPRESENTATIVE, AND SHALL BE REPAIRED BY THE CONTRACTOR AT NO COST TO THE OWNER.

ENVIRONMENTAL PROTECTION NOTES:

- STREAM CONSERVATION: THE CONTRACTOR SHALL CONDUCT OPERATIONS TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE TO PREVENT ANY DAMAGE TO PRIEST RIVER FROM POLLUTION BY DEBRIS, SEDIMENT, OR OTHER FOREIGN MATERIAL, OR FROM THE MANIPULATION OF EQUIPMENT AND/OR MATERIALS IN OR NEAR THE WATERWAYS. THE CONTRACTOR SHALL NOT RETURN DIRECTLY TO A STREAM, OR TO A DITCH IMMEDIATELY FLOWING INTO A STREAM, ANY WATER WHICH HAS BEEN USED FOR WASH PURPOSES OR OTHER SIMILAR OPERATIONS WHICH COULD CAUSE THIS WATER TO BECOME POLLUTED WITH SAND, SILT, CEMENT, OIL, OR OTHER IMPURITIES. IF THE CONTRACTOR WANTS TO USE RIVER / LAKE WATER FOR CONSTRUCTION PURPOSES, A TEMPORARY WATER USE PERMIT IS REQUIRED FROM IDAHO DEPARTMENT OF WATER RESOURCES. IF THE CONTRACTOR USES WATER FROM A STREAM, HE/SHE SHALL CONSTRUCT AN INTAKE OR TEMPORARY DAM TO PROTECT AND MAINTAIN WATER RIGHTS AND TO SUSTAIN FISH LIFE DOWNSTREAM. THESE TEMPORARY MEASURES SHALL BE REMOVED AND THE AREA RESTORED AT THE COMPLETION OF THE WORK
- DEWATERING WILL BE REQUIRED FOR THE CONSTRUCTION OF CONCRETE SUBSTRUCTURES AND GATES. THE COST OF DEWATERING IS TO BE INCLUDED IN THE CONTRACTOR'S PRICE BID.
- VISIBLY TURBID DISCHARGES FROM DEWATERING OPERATIONS OR EXCAVATION 3 ACTIVITIES SHALL NOT BE ALLOWED TO ENTER THE RIVER. ANY SUCH DISCHARGE SHALL BE (1) RETAINED IN AN APPROPRIATELY MAINTAINED UPLAND SETTLING BASIN, OR (2) FILTERED THROUGH CRUSHED STONE, SAND, HAY BALES, AND SILT SCREENING (EQUIVALENT OPENING SIZE OF U.S. SIEVE NUMBER 20).
- ALL NECESSARY PRECAUTIONS SHALL BE TAKEN TO PREVENT THE ENTRANCE OF FRESH CONCRETE INTO THE WATERS. EQUIPMENT, TOOLS, AND TRUCKS USED IN THIS PROJECT SHALL BE CLEANED IN SUCH A MANNER AS TO PREVENT WASH WATER FROM ENTERING ANY STREAM OR LAKE. WET CONCRETE IS HIGHLY TOXIC TO FISH.
- SPILLAGE OF OIL AND HAZARDOUS SUBSTANCES IS ESPECIALLY PROHIBITED BY SECTION 311 OF THE CLEAN WATER ACT OF 1977. MEASURES INCLUDING PROPER MAINTENANCE OF CONSTRUCTION EQUIPMENT, DESIGNATING FUEL/HAZARDOUS SUBSTANCES HANDLING AREAS TO ALLOW SPILLS TO BE CONTAINED BEFORE REACHING THE WATERWAY, INSTRUCTING PERSONNEL NOT TO DISPOSE OF OIL AND OTHER SUCH MATERIALS INTO DRAINS OR INTO THE WATERWAY DIRECTLY, AND OTHER NECESSARY PROCEDURES SHALL BE IMPLEMENTED PRIOR TO ANY CONSTRUCTION ACTIVITIES. IF IN SPITE OF SUCH PLANNING, OIL/HAZARDOUS SUBSTANCES ARE SPILLED INTO A WATER COURSE, IMMEDIATE NOTIFICATION SHALL BE GIVEN TO THE OWNER, OWNER'S REPRESENTATIVE, THE OWNER'S CONSTRUCTION MANAGER AND IDAHO DEPARTMENT OF ENVIRONMENTAL QUALITY. A CONTAINMENT BOOM AND A SUPPLY OF HAY, STRAW, OR OTHER ABSORBENT SHOULD BE RETAINED SO THAT IT MAY BE RAPIDLY DEPLOYED TO SOAK UP ANY POSSIBLE SPILLAGE, PENDING IDAHO DEPARTMENT OF ENVIRONMENTAL QUALITY ARRIVAL ON THE SCENE. THE USE OF CHEMICAL DISPERSING AGENTS AND EMULSIFIERS IS NOT AUTHORIZED WITHOUT PRIOR SPECIFIC FEDERAL OR STATE APPROVAL.
- A PRE-CONSTRUCTION NOTIFICATION WILL BE SUBMITTED TO THE U.S. ARMY CORPS OF 6. ENGINEERS FOR THE PROPOSED WORK TO BE PERFORMED BY THE OWNER UNDER NATIONWIDE PERMIT #3. THE CONTRACTOR SHALL COMPLY WITH THE TERMS AND CONDITIONS OF THE NATIONWIDE PERMIT AND THE PROVISIONS OF THE TITLE 5 OF ARTICLE 15 OF THE ENVIRONMENTAL CONSERVATION LAW.
- A SILT FENCE SHALL BE INSTALLED AROUND THE ENTIRE PERIMETER OF ANY STONE. TOPSOIL, WASTE, OR OTHER STOCKPILES THAT WILL NOT BE USED OR STABILIZED WITHIN 14 DAYS
- SEDIMENTS COLLECTED DURING DE-WATERING ARE TO BE DISPOSED OF AT A NON-HAZARDOUS SOLID WASTE APPROVED FACILITY, THESE MATERIALS ARE NOT TO BE RE-USED ON SITE AS FILL MATERIAL UNLESS APPROVED BY THE OWNER'S REPRESENTATIVE
- CONTRACTOR SHALL COMPLY WITH THE LOCAL NOISE ORDINANCE

M 1601 5th Avenue Suite 800 Seattle, Washington 9810 MACDONALD T +1 (425) 778 6243 W mottrnac.com	Client IDAHO DEPARTMENT OF WATER RESOURCE 322 Front Street Suite 648 P.O. Box 83720 Boise, Idaho 83702	ES						Designed Drawn Dwg check Scale at AN	J. Dawson T. Morrison	Eng check Coordination Approved Rev	S. Phillips	Title Priest Lake Water Management Project Outlet Dam Improvements
Cipwworkinghmmiports harbors\tad69807/dms259011376997 - Priest Lake Dam - Notes.dw	P (208) 287-4800 F (208) 287-6700	0 5/6/20 Rev Date	TM 90% SUBMITTAL Drawn Description	SK SP Ch'k'd App'd	Project Number 376997	в/о 2	Total 25	Drawing Nu	nber	GN-1		GENERAL NOTES AND ABBREVIATIONS

DAM NOTES: 1. ALL GATES MUST BE IN PLACE AND FUNCTIONAL PRIOR TO REMOVING COFFERDAMS. 2

3.

RIVFR

5.

BELOW

OPEN:

6.

ABUTM

ABBREVIATIONS:

ABUT

- AMERI ACI AISC AMER AWS AMER APPROX APPR BM BENCH B.O. BOTTO BOT BOTTO B.W. BOTH CENTE COMM COMM CONTR CDF CIP CAST-I CLR CLEAR CONCE CONC COMPL CPGW DIAME EASTIN EACH EA E.F. EACH
- EG FOR EX EQ. FOUAL EACH E.S E.W. EACH EOP EDGE **FI EVA** ETC AND S
- EXIST EX. EXIST FLUX (FCAW FCM

E.E.

GCP

GALV

HT

HMA

IBC

FT

- FRACT FRONT
- FEET GROUI
- GALVA HARD
- HOT M INTER

THE CONTRACTOR WILL NOT BE PERMITTED TO ERECT OR PLACE SCAFFOLDING OR OTHER TEMPORARY STRUCTURES OVER THE DAM WITHOUT THE WRITTEN APPROVAL OF THE OWNER'S REPRESENTATIVE. THE REQUEST FOR APPROVAL OF PROPOSED SCAFFOLDING OR TEMPORARY STRUCTURES OVER THE DAM MUST BE ACCOMPANIED BY PLANS OR SKETCHES OF THE SCAFFOLDING OR TEMPORARY STRUCTURES, INCLUDING PLANS FOR REMOVAL OF SAID ELEMENTS.

ANY SCAFFOLDING, TEMPORARY STRUCTURES, MASKING SYSTEM. CONTAINMENT COMPONENT OR TIE DOWNS, ETC. SHALL NOT INTERFERE WITH THE OPERABLE GATES.

DURING THE COURSE OF WORK UNDER THIS CONTRACT, CARE SHALL BE EXERCISED THAT NO MATERIAL IS DROPPED INTO THE

EACH YEAR, IN THE SPRING THE GATES ARE CLOSED AND PLACED INTO THE WATER TO BEGIN THE RECREATION SEASON AND IN THE WINTER THE GATES ARE OPEN AND REMOVED FROM THE WATER TO END THE RECREATION SEASON APPROXIMATE OPENING AND CLOSING DATES FOR THE DAM ARE AS SCHEDULED

2020/2021

NOVEMBER 1 CLOSED: AFTER APRIL 1

THE CONTRACTOR SHALL SCHEDULE AND PROGRESS WORK SUCH THAT THE DAM IS OPEN FOR USE WITHIN THE DATES NOTED ABOVE.

THE CONTRACTOR SHALL LIMIT THEIR WORK REQUIRING USE OF ANY WATER CONTROL STRUCTURE TO THE TIME PERIOD FROM "OPEN" TO "CLOSED" NOTED ABOVE.

THE CONTRACTOR SHALL NOT PERFORM ANY WORK DURING THE PEAK RECREATIONAL SEASON IN THE TIME PERIOD FROM "CLOSED" TO "OPEN" NOTED ABOVE WHICH AFFECTS THE OPERATION OF THE GATES WITHOUT PRIOR APPROVAL FROM THE OWNER'S REPRESENTATIVE

MENT MENT RICAN CONCRETE INSTITUTE RICAN INSTITUTE OF STEEL CONSTRUCTION RICAN WELDING SOCIETY OXIMATELY HMARK OM OF OM WAYS ERLINE HINICATIONS	MAX MIN MLW MP N NAD83 NAVD88	IDAHO TRANSPORTATION DEPARTMENT IDAHO WATER RESOURCE BOARD LIMITS OF CONSTRUCTION MAXIMUM MINIMUM MEAN LOW WATER MAGNETIC PARTICLE TESTING NORTHING OR NORTH NORTH AMERICAN DATUM OF 1983 NORTH AMERICAN VERTICAL DATUM OF 1988
		ON CENTER
ROLLED DENSITY FILL -IN-PLACE		ORDINARY HIGH WATER PARTIAL PENETRATION GROOVE WELD
-IN-PLACE R		PROCEDURE QUALIFICATION RECORD
RETE		QUALITY ASSURANCE
PLETE PENETRATION GROOVE WELD		QUALITY CONTROL
ETER	REF	REFERENCE
NG		REAR FACE
	REINF	
FACE	RT	RADIOGRAPHIC TESTING
EXAMPLE	S SIM	SOUTH
L SIDE	SIM	SIMILAR SHIELDED METAL ARC WELDING
WAY	SIVIAW	STANDARD
	STA	STANDARD
ATION	T.O.	TOP OF
SO ON	TYP	TYPICAL
ING	UT	ULTRASONIC TESTING
CORED ARC WELDING	VIF	VERIFY IN FIELD
TURE CRITICAL MEMBER	WP	WORKING POINT
T FACE	WPS	WELD PROCEDURE SPECIFICATION
	WSEL	WATER SURFACE ELEVATION
IND CONTROL POSITION	W/	WITH
ANIZED NESS TESTING	@	AT MINUTES OR FEET
NESS TESTING /IX ASPHALT		SECONDS OR INCHES

GENERAL NOTES - CONT'D

CONCRETE NOTES:

- 1. ALL STRUCTURAL CONCRETE WORK SHALL COMPLY WITH ACI 301-10 AND TO THE REQUIREMENTS IN SPECIFICATION SECTION 033000.
- ALL REINFORCED CAST-IN-PLACE CONCRETE CONSTRUCTION SHALL CONFORM TO THE ACI "MANUAL OF CONCRETE PRACTICE", "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE" (ACI 318-14), AND "ACI DETAILING MANUAL" (ACI SP 66), EXCEPT AS MODIFIED BY THE CONTRACT DRAWINGS AND SPECIFICATIONS
- 3. CONCRETE FOUNDATIONS SHALL MEET THE FOLLOWING MINIMUM REQUIREMENTS:

	f'c	W/C RATIO
APRON SLAB, KEYWAY, WALLS	5000 PSI	0.40
PIERS	5000 PSI	0.40

CONCRETE SHALL BE IN ACCORDANCE WITH SPECIFICATION SECTION 033000 CAST-IN-PLACE CONCRETE

- ALL REINFORCING STEEL SHALL HAVE MINIMUM YIELD STRENGTH, fy=60 KSI AND SHALL BE NEW DEFORMED BILLET-STEEL CONFORMING TO ASTM A615, GRADE 60.
- ALL DETAILING, BENDING, PLACEMENT AND SUPPORT OF REINFORCING SHALL CONFORM TO THE 5 STANDARDS CITED.
- CLEAR CONCRETE COVER OVER PRINCIPAL REINFORCING SHALL BE 3" WHEN CONCRETE IS CAST AGAINST OR PERMANENTLY IN CONTACT WITH GROUND AND 2" AT ALL OTHER LOCATIONS.
- ALL STRUCTURAL MEMBERS SHALL BE CAST MONOLITHICALLY FOR THEIR FULL DEPTH, UNLESS OTHERWISE NOTED.
- ALL CONSTRUCTION JOINTS SHALL BE THOROUGHLY CLEANED, WETTED AND SPLASHED WITH CEMENT GROUT JUST PRIOR TO PLACING NEW CONCRETE.
- THE SPACING OF REINFORCING SHOWN ON THE CONTRACT DRAWINGS IS THE MAXIMUM PERMITTED. IT MAY BE REDUCED FOR CONSTRUCTION CONSIDERATIONS, BUT IS NOT TO BE EXCEEDED.
- 10. WHERE INDICATED ON THE PLANS, ALL STRUCTURAL CONCRETE SHALL BE REMOVED TO THE DEPTH SPECIFIED, OR TO THE DEPTH AS ORDERED BY THE OWNER'S REPRESENTATIVE. BEFORE STARTING THIS WORK, THE CONTRACTOR SHALL SUBMIT A PLAN SHOWING THE PROPOSED METHOD, EQUIPMENT, AND SEQUENCE FOR THE REMOVAL WORK TO THE OWNER'S REPRESENTATIVE FOR APPROVAL.
- 11. EXPOSED REINFORCING STEEL THAT WILL REMAIN IN THE STRUCTURE SHALL BE PROTECTED FROM DAMAGE, AND BLAST-CLEANED TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE
- ALL EXPOSED EDGES OF CONCRETE ARE TO BE CHAMFERED UNLESS OTHERWISE NOTED.
 ALL FORMING HARDWARE SUCH AS TIES AND "ALL-THREADS" THAT ARE TO REMAIN IN THE CONCRETE SHALL BE ELECTROPLATED OR MADE OF A NON-FERROUS MATERIAL TO PREVENT CORROSION. 14. WHERE DRILLING AND GROUTING REINFORCING BARS, THE DIAMETER OF THE DRILLED HOLE SHALL BE AS
- RECOMMENDED BY THE EPOXY GROUT MANUFACTURER
- 15. ALL CONCRETE ELEMENTS SHALL CONTAIN AN AIR ENTRAINMENT ADMIXTURE

REINFORCING BAR EMBEDMENT/ LAP SPLICE SCHEDULE

	TOP	BARS	OTHER BARS						
BAR SIZE	EMBEDMENT	LAP	EMBEDMENT	LAP					
	5000 PSI	5000 PSI	5000 PSI	5000 PSI					
#3	17"	22"	13"	17"					
#4	22"	29"	17"	22"					
#5	28"	36"	21"	28"					
#6	33"	43"	25"	33"					
#7	48"	63"	37"	48"					
#8	55"	72"	42"	55"					

NOTES

- TOP BARS ARE THOSE WHICH ARE ORIENTED HORIZONTAL AND HAVE MORE THAN 12" OF CONCRETE
- BELOW THE BAR
- SPLICE BOTTOM BARS AT SUPPORTS. 2
- SPLICE UPPER BARS IN MIDDLE ¹/₃ OF SPAN. WHERE CONCRETE DEPTH PRECLUDES FULL
- EMBEDMENT, PROVIDE 90 HOOK.
- PROVIDE CONCRETE PROTECTION FOR
- REINFORCEMENT AS DESCRIBED IN ACI 318 CHAPTER 20. EMBEDMENT AND LAP SPLICE LENGTHS SHOWN ARE 6. APPLICABLE TO ASTM A615 GR. 60 REINFORCING BARS.

STEEL NOTES:

- ALL STRUCTURAL STEEL INCLUDING CONNECTIONS AND MISCELLANEOUS STEEL SHALL CONFORM TO THE REQUIREMENTS IN SPECIFICATION SECTION 051200.
- ALL GALVANIC SHOP APPLIED COATINGS FOR STRUCTURAL STEEL SHALL CONFORM TO THE REQUIREMENTS SPECIFIED IN SPECIFICATION SECTION 050500.
- ALL STEEL FABRICATION, FURNISHING, DELIVERY, AND ERECTION OF STRUCTURAL STEEL AND ITS COMPONENTS SHALL BE PERFORMED IN ACCORDANCE WITH AWS D1.1 AND AISC MANUAL OF STEEL 3 CONSTRUCTION (14TH EDITION).
- ALL STEEL SHALL BE GALVANIZED IN ACCORDANCE WITH SPECIFICATION SECTION 050500. SHOP DRAWINGS OF ALL STRUCTURAL STEEL SHALL BE PREPARED AND SUBMITTED TO THE OWNER'S REPRESENTATIVE FOR REVIEW IN ACCORDANCE WITH AISC STANDARDS SHOWING ALL SHOP AND ERECTION DETAILS INCLUDING CUTS, COPES, CONNECTIONS, ETC.
- FIELD BURNING OF HOLES WILL NOT BE PERMITTED. ALL WELDING ELECTRODES SHALL CONFORM TO THE E-70 SERIES AS PER AWS STRUCTURAL WELDING CODE D1 1/D1 1M
- CARE SHALL BE TAKEN TO AVOID CAUSING DAMAGE TO EXISTING MEMBERS WHICH ARE TO REMAIN IN 8 PLACE.

J-SEAL NOTES:

J-SEAL REQUIREMENTS: THE PROPOSED RADIAL GATE J-SEALS SHALL HAVE THE SAME CROSS-SECTIONAL DIMENSIONS AS THE EXISTING J-SEALS. THE CONTRACTOR SHALL MEASURE THE EXISTING J-SEAL DIMENSIONS AND/OR DEVELOP THE DIMENSIONS BASED ON THE ORIGINAL 1978 DRAWINGS IN ORDER TO DEVELOP THE PROPOSED J-SEAL DRAWINGS. THE CONTRACTOR SHALL SUBMIT J-SEAL MATERIAL INFORMATION AND J-SEAL SHOP DRAWINGS TO THE OWNER'S REPRESENTATIVE FOR APPROVAL

2.

DELIVERY, STORAGE, AND HANDLING OF J-SEALS: STORE J-SEALS IN A PLACE WHICH PERMITS FREE CIRCULATION OF AIR, MAINTAINS A TEMPERATURE OF 70 DEGREES F OR LESS, AND PREVENTS THE RUBBER FROM BEING EXPOSED TO THE DIRECT RAYS OF THE SUN. KEEP J-SEALS FREE OF OILS, GREASE, AND OTHER MATERIALS WHICH WOULD DETERIORATE THE RUBBER. J-SEALS SHALL NOT BE DISTORTED DURING HANDLING.

3.

PRODUCTS – J-SEALS: J-SEALS SHALL BE RUBBER SEALS OF THE MOLD TYPE ONLY, SHALL BE COMPOUNDED OF NATURAL RUBBER, SYNTHETIC POLYISOPRENE, OR A BLEND OF BOTH, AND SHALL CONTAIN REINFORCING CARBON BLACK, ZINC OXIDE, ACCELERATORS, ANTIOXIDANTS, VULCANIZING AGENTS, AND PLASTICIZERS. PHYSICAL CHARACTERISTICS OF THE J-SEALS SHALL MEET THE FOLLOWING REQUIREMENTS:

PHYSICAL TEST	TEST VALUE	TEST METHOD SPECIFICATION
TENSILE STRENGTH	2500 PSI (MIN.)	ASTM D412
ELONGATION AT BREAK	450% (MIN.)	ASTM D412
300 PERCENT MODULUS	900 PSI (MIN.)	ASTM D412
DUROMETER HARDNESS (SHORE TYPE A)	60 TO 70	ASTM D2240
WATER ABSORPTION	5% BY WEIGHT (MAX)	ASTM D471
COMPRESSION SET	30% TENSILE STRENGTH (MIN.)	ASTM D395
TENSILE STRENGTH (AFTER AGING 48 HRS)	80% TENSILE STRENGTH (MIN.)	ASTM D572

THE "WATER ABSORPTION" TEST SHALL BE PERFORMED WITH DISTILLED WATER. THE WASHED SPECIMEN SHALL BE BLOTTED DRY WITH FILTER PAPER OR OTHER ABSORBENT MATERIAL AND SUSPENDED BY MEANS OF SMALL GLASS RODS IN THE OVEN AT A TEMPERATURE OF 158 DEGREES F PLUS OR MINUS 2 DEGREES F FOR 22 HOURS PLUS OR MINUS 1/4 HOUR. THE SPECIMEN SHALL BE REMOVED, ALLOWED TO COOL TO ROOM TEMPERATURE IN AIR, AND WEIGHED. THE WEIGHT SHALL BE RECORDED TO THE NEAREST OUNCE AS W1 (W1 IS DEFINED IN ASTM D471). THE IMMERSION TEMPERATURE SHALL BE 158 DEGREES F PLUS OR MINUS 1 DEGREE F AND THE DURATION OF IMMERSION SHALL BE 166 HOURS

ASTM PUBLICATIONS:

ASTM D395 (2016; E 2017) STANDARD TEST METHODS FOR RUBBER PROPERTY - COMPRESSION SET ASTM D412 (2016) STANDARD TEST METHODS FOR VULCANIZED RUBBER AND THERMOPLASTIC ELASTOMERS - TENSION

ASTM D413 (1998; R 2017) STANDARD TEST METHODS FOR RUBBER PROPERTY - ADHESION TO FLEXIBLE SUBSTRATE

ASTM D471 (2016A) STANDARD TEST METHOD FOR RUBBER PROPERTY - EFFECT OF LIQUIDS ASTM D572 (2004; R 2010) RUBBER DETERIORATION BY HEAT AND OXYGEN

ASTM D2240 (2015; E 2017) STANDARD TEST METHOD FOR RUBBER PROPERTY - DUROMETER HARDNESS

J-SEAL FABRICATION AND INSTALLATION:

J-SEALS SHALL BE CONTINUOUS OVER THE FULL LENGTH. J-SEALS SHALL BE ACCURATELY FITTED AND DRILLED FOR PROPER INSTALLATION. BOLT HOLES SHALL BE DRILLED IN THE J-SEALS BY USING PREPARED TEMPLATES OR THE RETAINER BARS AS TEMPLATES. SPLICES IN J-SEALS SHALL BE FULLY MOLDED, DEVELOP A MINIMUM TENSILE STRENGTH OF 50 PERCENT OF THE UNSPLICED SEAL, AND OCCUR ONLY AT LOCATIONS SHOWN ON THE DRAWINGS. ALL VULCANIZING OF SPLICES SHALL BE DONE IN THE SHOP. THE VULCANIZED SPLICES BETWEEN MOLDED CORNERS AND STRAIGHT LENGTHS SHALL BE LOCATED AS CLOSE TO THE CORNERS AS PRACTICABLE. SPLICES SHALL BE ON A 45-DEGREE BEVEL RELATED TO THE "THICKNESS" OF THE J-SEAL. THE SURFACES OF FINISHED SPLICES SHALL BE SMOOTH AND FREE OF IRREGULARITIES. J-SEALS SHALL BE ADJUSTED AFTER INSTALLATION SO THAT THEY ARE SLIGHTLY COMPRESSED IN THE CLOSED, UNWATERED CONDITION TO PREVENT EXCESSIVE DEPRESSION AND WEAR IN THE CLOSED, WATERED CONDITION. BEFORE OPERATING THE GATES, A SUITABLE LUBRICANT SHALL BE APPLIED TO THE J-SEAL RUBBING PLATES TO PROTECT THE RUBBER.

METAL FABRICATION NOTES:

- SPECIFICATIONS.
- ALL STEEL SHALL BE OF DOMESTIC ORIGIN.
 - BOLTED CONNECTIONS:
 - A.)

 - C.)
- FACILITATE GALVANIZING.

QUALITY CONTROL (QC) / QUALITY ASSURANCE (QA):

REPAIR REQUIREMENTS:

- ADDITIONAL COST TO THE OWNER. 3
- GOVERNING WELDING SPECIFICATION:
- - A.)
 - B.)

 - D.)
- 6. WELDER, WELDING OPERATOR, AND TACKER REQUIREMENTS:

 - AWS D1.1.
- 7. TEMPORARY AND TACK WELDS:

 - SUBMERGED ARC WELD.

 - C.)
- 8. BOLTED CONNECTIONS:
 - A.)

 - EDITION OF AISC
- esigned J. Dawson 1601 5th Avenue Suite 800 RAF . Morriso **IDAHO** Seattle, Washington 98101 DEPARTMENT OF WATER RESOURCES Owg check 322 Front Street Suite 648 P.O. Box 83720 FOR BID cale at ANSI D Status T +1 (425) 778 6243 Boise, Idaho 83702 W mottmac.com P (208) 287-4800 F (208) 287-6700 Drawing Number TM 90% SUBMITTAL Project Numbe 5/6/20 SK SP 376997 3 25 GN-2 Drawn Description Rev Date Ch'k'd App'o Notes.dwg Jun 12, 2020

Μ Μ мотт MACDONALD 1. THESE NOTES ARE INTENDED TO BE A GUIDELINE. THESE NOTES ARE NOT A COMPLETE LISTING OF ALL REQUIREMENTS. THE CONTRACTOR SHALL PERFORM ALL WORK IN ACCORDANCE WITH THE

THE DIMENSIONAL TOLERANCE OF EACH INDIVIDUAL MEMBER SHALL BE IN ACCORDANCE WITH THE GOVERNING CODE, UNLESS OTHERWISE NOTED IN THE CONTRACT DOCUMENTS. THE DIMENSIONAL TOLERANCE OF THE COMPLETED ASSEMBLY SHALL ALSO BE IN ACCORDANCE WITH THE LEAST RESTRICTIVE TOLERANCE OF THE INDIVIDUAL MEMBERS.

> MEMBERS OF CONNECTIONS SHALL BE MATCH MARKED AS NECESSARY FOR ASSEMBLY AFTER CLEANING AND GALVANIZING OF THE CONNECTION INNER PLIES. INNER PLIES OF ALL BOLTED CONNECTIONS SHALL BE CLEANED.

ALL BOLTING SHALL BE PERFORMED IN ACCORDANCE WITH AISC. THIS SHALL INCLUDE BOLT TENSION VERIFICATION AND SAMPLING OF FASTENERS.

5. ALL EXPOSED EDGES ON PLATES AND SHAPES SHALL BE CHAMFERED TO A MINIMUM RADIUS OF 1/16" TO

THE CONTRACTOR/FABRICATOR IS RESPONSIBLE FOR QC AND THE OWNER'S REPRESENTATIVE MAY PERFORM QA AS DESCRIBED IN AISC. ANY QA PERFORMED BY THE OWNER'S REPRESENTATIVE WILL NOT RELIEVE THE CONTRACTOR OF RESPONSIBILITY TO PERFORM BOTH QC AND QA INSPECTION TESTS TO ENSURE THAT ALL PRODUCTS MEET THE REQUIREMENTS OF THE CONTRACT DOCUMENTS AND SHALL NOT RELIEVE THE CONTRACTOR OF RESPONSIBILITY CONCERNING UNACCEPTABLE MATERIALS AND WORKMANSHIP AND THE RESPONSIBILITY TO ACCEPTABLY REPAIR OR REPLACE THE SAME. THE OWNER'S REPRESENTATIVE WILL INSPECT ALL STEEL AT THE TIME OF DELIVERY FOR WORKMANSHIP, FIT. AND CONFORMANCE TO THE CONTRACT DOCUMENTS, ANY MATERIAL WITH DEFECTS, DEFICIENCIES, UNAPPROVED CHANGES OR REPAIRS WILL BE CAUSE FOR IMMEDIATE REJECTION. REJECTED STEEL SHALL BE REMOVED AND REPLACED, OR REPAIRED BY A PROCEDURE APPROVED BY THE OWNER'S REPRESENTATIVE AT NO ADDITIONAL COST TO THE OWNER

ANY REPAIRS TO STRUCTURAL STEEL MEMBER SHALL NOT BE PERFORMED UNTIL THE REPAIR PROCEDURE HAS BEEN APPROVED BY THE ENGINEER OF RECORD.

ANY MEMBER THAT HAS BEEN REPAIRED, OR IS BEING REPAIRED, WITHOUT PRIOR APPROVAL FROM THE ENGINEER OF RECORD SHALL BE REJECTED, AND A NEW MEMBER SHALL BE FABRICATED AT NO

ANY MEMBER WITH UNAPPROVED MILL CERTIFICATIONS, CATALOG CUT SHEETS, CHANGES OR REPAIRS, HAS MATERIAL DEFECTS, DISCONTINUITIES, MISPLACED BOLT HOLES, OR HAS BEEN WELDED BY AN UNQUALIFIED WELDER WILL BE CAUSE FOR IMMEDIATE REJECTION. REJECTED STEEL SHALL BE REMOVED AND REPLACED, OR REPAIRED BY A PROCEDURE APPROVED BY THE ENGINEER OF RECORD OR OWNER'S REPRESENTATIVE AT NO ADDITIONAL COST TO THE OWNER.

> THE FABRICATION AND WELDING OF ALL WELDS ON STEEL MEMBERS SHALL BE PERFORMED IN ACCORDANCE WITH THE CURRENT EDITION OF THE AMERICAN WELDING SOCIETY'S STRUCTURAL WELDING CODE - D1.1/D1.1M.

5. SHOP OR FIELD WELDING SHALL NOT BE PERFORMED ON ANY STEEL MEMBER UNTIL:

MILL CERTIFICATIONS AND CATALOG CUT SHEETS HAVE BEEN SUBMITTED AND EITHER "APPROVED" OR "APPROVED AS NOTED BY THE OWNER'S REPRESENTATIVE". A COPY OF THE WELDER QUALIFICATIONS HAS BEEN SUBMITTED AND APPROVED BY THE

OWNER'S REPRESENTATIVE, FOR ALL PERSONNEL WHO WILL BE WELDING ON THE WORK THE WELD PROCEDURE SPECIFICATION (WPS) HAS BEEN SUBMITTED AND APPROVED, BY THE OWNER'S REPRESENTATIVE, FOR EACH JOINT IN THE WORK. THE PROCEDURE QUALIFICATION RECORD (PQR) HAS BEEN SUBMITTED AND APPROVED, BY

THE OWNER'S REPRESENTATIVE, FOR EACH PROCESS TO BE USED IN THE WORK.

ALL TACK, FILLET, AND CPGW'S SHALL BE PERFORMED BY WELDERS CURRENTLY QUALIFIED FOR THE POSITION, PROCESS AND LOCATION (FIELD OR SHOP) TO BE USED IN THE WORK IN

ACCORDANCE WITH AWS D1.1. ALL PPGW'S SHALL BE PERFORMED BY WELDERS CURRENTLY QUALIFIED FOR THE POSITION,

PROCESS AND LOCATION (FIELD OR SHOP) TO BE USED IN THE WORK IN ACCORDANCE WITH

PREHEAT IS REQUIRED FOR FIELD WELDED TEMPORARY OR TACK WELDS.

PREHEAT IS REQUIRED WHEN A TACK WELD IS NOT INCORPORATED INTO THE FINAL


TEMPORARY OR TACK WELDS NOT INCORPORATED INTO THE FINAL WELD SHALL BE GROUND FLUSH WITH THE ORIGINAL SURFACE.

BOLTING OR DRILLING OF HOLES SHALL NOT BE PERFORMED ON ANY STEEL MEMBER UNTIL THE MILL CERTIFICATIONS AND CATALOG CUT SHEETS HAVE BEEN SUBMITTED AND EITHER APPROVED" OR "APPROVED AS NOTED BY THE OWNER'S REPRESENTATIVE"

BOLT HOLES SHALL NOT BE INSTALLED UNLESS SPECIFICALLY AND ACCURATELY

DIMENSIONED ON THE SHOP DRAWINGS, MAXIMUM AND MINIMUM BOLT SPACING, EDGE DISTANCE. STITCH AND SEALING SPACINGS SHALL BE IN ACCORDANCE WITH THE LATEST

Eng check	S. Phi	illips	Title	Priest Lake Water
Coordination				Management Project
Approved				Outlet Dam Improvements
Rev		Security		
				GENERAL NOTES



NOTES

Μ

MOTT MACDONALD

LEGEND

1.

- TOPOGRAPHIC AND BATHYMETRY SOURCE, MOTT MACDONALD DATA COLLECTION, AUGUST-SEPTEMBER 2018. HORIZONTAL DATUM: NAD83, IDAHO STATE PLANE, WEST ZONE VERTICAL DATUM: NAVD88. AERIAL SOURCE: DELPHIS, AUGUST 2018, UAV AERIAL 2.
- 3. 4.
- PHOTOGRAMMETRY.

1601 5th Avenue	Client	_									Designed	E. Sheesle	ey .	Eng check	S. Phillips	^{Tite} Priest Lake Water
Suite 800 Seattle, Washington 98101	IDAHO IDAHO								AFT^{\frown}	\	Drawn	T. Morrisor	n	Coordination	n	Management Project
Seattle, Washington 96101	DEPARTMENT OF WATER RESOURC	≡s)	Dwg check			Approved		Outlet Dam Improvements
T +1 (425) 778 6243 W mottmac.com	P.O. Box 83720 Boise, Idaho 83702								RBID		Scale at AN		atus	Rev	Security	
w mounac.com	P (208) 287-4800															OVERALL SITE PLAN -
	F (208) 287-6700	(5/6/20	ТМ	90% SUBMITTAL	SK	SP	Project Number	B/O	Total	Drawing Nu	mber		א חר		EXISTING CONDITIONS
		R	ev Date	Drawn	Description	Ch'k'd	App'd	376997	4	25			, c	GP-1		

20

SCALE IN FEET

GROUND PHOTO 1



GROUND PHOTO 4



GROUND PHOTO 7



GROUND PHOTO 2



GROUND PHOTO 5



GROUND PHOTO 8







Μ	1601 5th Avenue	Client								_	Designed	J. Dawson	Eng ch	eck S. Phillips	Priest Lake Water
M	Suite 800	IDAHO IDAHO						(DR	ΛCT		Drawn	T. Morrison	Coordi	nation	Management Project
	Seattle, Washington 98101	DEPARTMENT OF WATER RESOURCES 322 Front Street Suite 648)	Dwg check		Approv	ed	Outlet Dam Improvements
	T +1 (425) 778 6243	P.O. Box 83720 Boise, Idaho 83702						FUI	R BID		Scale at AN	SID Status	Rev	Security	
	W mottmac.com	P (208) 287-4800													PHOTOS SHEET -
		F (208) 287-6700	0	5/6/20	TM	90% SUBMITTAL	SK SP	Project Number	B/O		Drawing Nur				EXISTING CONDITIONS 1
			Rev	Date	Drawn	Description	Ch'k'd App'd	376997	5	25			PH-1		
C:\pwworking\hmm\ports_harbors\tad69807\dms25901\37	76997 - Priest Lake Dam - Notes.dwg Jun 12, 2020 -	5:25PM Tadlock, Brice													

GROUND PHOTO 3



GROUND PHOTO 6



GROUND PHOTO 9



GROUND PHOTO 10



GROUND PHOTO 13



GROUND PHOTO 11



GROUND PHOTO 14



NOTE

1. FOR LOCATION OF GROUND PHOTOS 12, 13, AND 14, SEE DWG. C-1.

M MOTT MACDONALD	1601 5th Avenue Suite 800 Seattle, Washington 98101 T +1 (425) 778 6243 W mottmac.com	Client	IDAHO DEPARTMENT OF WATER RESOURCES 322 Front Street Suite 648 P.O. Box 83720 Boise, Idaho 83702 P (208) 287-4800							- \		Designed J. Dawson Drawn T. Morrison Dwg check	C	ng check coordination pproved ev	S. Phillips	Titl	Priest Lake Water Management Project Outlet Dam Improvements PHOTOS SHEET -
		#ESOURCE	F (208) 287-6700	0 5	/6/20	TM 9	90% SUBMITTAL SK	SP	Project Number	B/O	Total	Drawing Number		<u>^</u>			EXISTING CONDITIONS 2
				Rev Dat	ie [Drawn D	Description Ch'k'd	App'd	376997	0	25		PH-:	2			
pwworking/hmm/ports_harbors/tad69807/dms259011376997 - Priest Lake Dam - Notes.dwg Jun 12, 2020 - 525PM Tadlock, Brice																	



GROUND PHOTO 12





WORK ACTIVITIES SHALL OCCUR WITHIN THE DEFINED LIMITS OF CONSTRUCTION. LAYDOWN AND ACCESS AREA SHOWN REPRESENTS GENERAL LOCATION AVAILABLE TO CONTRACTOR FOR STORAGE OF EQUIPMENT, MATERIALS, AND FIELD OFFICES. LIMITS OF AVAILABLE LAYDOWN AND ACCESS AREAS MAY VARY AND WILL BE DETERMINED BY OWNER'S REPRESENTATIVE. USE OF THESE AREAS SHALL BE LIMITED TO STORAGE OF EQUIPMENT AND MATERIALS.

S. KOKANEE PARK LOOP

- THE CONTRACTOR MAY USE LAMB CREEK LANE FOR ACCESS TO THE SITE AND LAYDOWN AREA BUT MUST TAKE STEPS TO MINIMIZE DAMAGE DUE TO CONSTRUCTION OPERATIONS.
- CONSTRUCTION ACTIVITIES, TEMPORARY STAGING, OR PARKING OF ANY KIND IS NOT ALLOWED IN THE ADJACENT KOKANEE PARK OR HWY 57. CONTRACTOR SHALL CONFINE ALL REFUELING OF EQUIPMENT TO THE
- CONSTRUCTION ENTRANCE PAD AREA AND SUBMIT A PLAN TO BE APPROVED BY THE OWNER'S REPRESENTATIVE.
- CONTRACTOR SHALL NOT RESTRICT ACCESS TO KOKANEE PARK OR HWY 57 DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR MAINTENANCE OF TRAFFIC DURING CONSTRUCTION TO ENSURE ACCESS TO KOKANEE PARK AND HWY 57 DURING CONSTRUCTION.
- DURING NON-WORKING HOURS, ALL CONSTRUCTION EQUIPMENT SHALL BE STORED IN AN AREA APPROVED BY THE OWNER'S REPRESENTATIVE.
- ALL WORK AREAS SHOULD BE COMPLETELY FENCED, CONFORMING WITH OSHA REGULATIONS, TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE, TO PROTECT THE PUBLIC AND PREVENT UNAUTHORIZED ENTRY. THE COST OF THIS WORK SHALL BE INCLUDED IN THE CONTRACTOR'S BID.
- CONTRACTOR TO VERIFY AVAILABILITY OF EXISTING UTILITIES AND PROVIDE NECESSARY UTILITY CONNECTIONS TO ACCOMMODATE THEIR OPERATIONS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR RETURNING ALL LAYDOWN AND ACCESS AREAS INCLUDING CONSTRUCTION ENTRANCES TO PRE-EXISTING CONDITIONS.
- ALL PORTIONS OF THE LAYDOWN AND ACCESS AREAS WHERE TRAFFIC OR LOADING COMPACTS THE NATIVE SOILS SHALL BE PLOWED OR TILLED TO A DEPTH OF 1.5 FEET BEFORE BEING RESTORED.
- ANY DAMAGE CAUSED BY THE CONTRACTOR TO THE EXISTING FACILITIES OR PAVING SHALL BE REPAIRED TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE AND IDAHO TRANSPORTATION DEPARTMENT (ITD) AT NO ADDITIONAL COST TO THE OWNER.

12

13

EXISTING POWER

AND COMM

LEGEND

my.

PROVIDE NEW PAVED APPROACH, SEE DWG. M-2

5

EXISTING SWING GATE

EXISTING-

M

OVERHEAD POWER LINES

Μ

мотт

MACDONALD

--- PROPERTY LINES - ORDINARY HIGH WATER (OHW) - A - PIER ACCESS ROAD

- P POWER LINE
- POWER UTILITY TRENCH (VERIFY IN FIELD)
- LOC LIMITS OF CONSTRUCTION
- TEMPORARY FENCING ____
- PHOTO NUMBER (SEE DWG. PH-2) (\mathbf{X})

LIGHT POLE

(VERIFY IN FIELD)

ACCESS ROAD EASEMENT

LAYDOWN AND ACCESS AREA

NO CONSTRUCTION ACCESS 10'-0" MIN. EXISTING STRUCTURE Α EXISTING 30 FT COMMON ACCESS AND UTILITY EASEMENT, SEE NOTES 14

> ACCESS ROAD, **APPROXIMATELY 625 FT**

EXISTING VEGETATION INCLUDING TREES AND TREE ROOTS TO BE PROTECTED OUTSIDE THE LAYDOWN AND ACCESS AREA (TYP.)

ACCESS TO

15'-0" MIN

CONTRACTOR LAYDOWN -AND ACCESS AREA, TYP.

TEMPORARY FENCE

EXISTING PIER

PROPERTY LINE, TYP.

	5' ±	10
EXISTING GRADE	3H:1V, TYP.	2%
		<u>8888888888888888888888888888888888888</u>

EXISTING SITE PLAN EXISTING PRIVATE ROAD, MAINTAIN ACCESS. NO 30


TEMPORARY CONSTRUCTION


ACCESS GATE, SEE DWG. C-5


S. KOKANEE PARK LOOP

ENTRANCE (20-FT WIDE X 80-FT LONG) PROVIDE CHAINLINK FENCING AND


			//				S		IN FEET				
1601 5th Avenue	Client											Designed	J. Dawson
Suite 800	IDAH0	IDAHO								ΔFT `	\backslash	Drawn	T. Morrison
Seattle, Washington 98101	Hart	DEPARTMENT OF WATER RESOURCES)	Dwg check	
T +1 (425) 778 6243		322 Front Street Suite 648 P.O. Box 83720							FOF	RBID		Scale at ANS	SID Status
W mottmac.com	A BO	Boise, Idaho 83702 P (208) 287-4800										As No	ted
	RESOURCE	F (208) 287-6700	0	5/6/20	ТМ	90% SUBMITTAL	SK	SP	Project Number	B/O		Drawing Nur	nber
			Rev	Date	Drawn	Description	Ch'k'd		376997	7	25		
\tad69807\dms25901\376997 - Priest Lake Dam - Site Plans.dwg Jun 12, 202	20 - 5:25PM Tadlock, Brice												








TEMPORA	ARY COFFE	RDAN



	(,	0	5/6/20	TM	90% SUBMITTAL
		Rev	Date	Drawn	Description

		TI I)		Dwg o
	FUF					Scale 1
997		в/о 10		Total	25	Drawi



NOTES:


- 1. INSTALL TEMPORARY SEDIMENT CONTROL BARRIERS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS AND SPECIFICATIONS. THE DIMENSIONS SHOWN ARE GENERAL GUIDELINES.
- 2. PLACE SEDIMENT BARRIERS TO FOLLOW THE SLOPE CONTOURS. METAL POSTS OR WOOD STAKES MAY BE USED.
- 3. ENSURE THAT RUNOFF PASSES THROUGH THE SILT FENCE AND NOT AROUND THE FENCE.
- 4. THE NEED FOR TEMPORARY SEDIMENT CONTROL DEVICES ARE DETERMINED BY SITE DESIGN. SPACE SILT FENCES IN ACCORDANCE WITH THE SILT FENCE SPACING TABLE.
- 5. EXTEND OR JOIN SILT FENCE USING SILT FENCE LAP WITH NESTED POSTS.
- 6. REMOVE SEDIMENT FROM THE UPSLOPE SIDE OF SILT FENCES WHEN ACCUMULATION HAS REACHED THE EFFECTIVE HEIGHT OF THE BARRIER.
- 7. SILT CURTAIN SHALL BE A MAXIMUM OF 100 FEET LONG FOR EACH SECTION OF CURTAIN REQUIRED. END SECTIONS SHALL TERMINATE 10 FEET BEYOND THE LIMIT OF DISTURBANCE.
- 8. THE SILT CURTAIN SHALL BE PLACED AS CLOSE TO THE WORK AS POSSIBLE WITHOUT INTERFERING WITH CONSTRUCTION OPERATIONS.
- THE CONTRACTOR SHALL CONTINUALLY MONITOR THE INSTALLATION, TAKING INTO ACCOUNT WEATHER PATTERNS AND PREVAILING WIND DIRECTIONS THAT MAY AFFECT WATER LEVELS, VELOCITY AND MOVEMENT OF THE SILT CURTAIN.
- 10. THE SILT CURTAIN SHALL BE REMOVED BY PULLING TOWARD THE SHORE TO MINIMIZE ESCAPE OF SEDIMENTS INTO THE WATERWAY.
- 11. THE WEIGHTED ANCHORING SYSTEM SHALL BE A TYPE THAT ALLOWS THE CURTAIN TO CONFORM TO THE CONTOUR OF THE BOTTOM OF THE WATERWAY.
- 12. CONSTRUCTION, DISTURBANCE AND LAYDOWN AREAS SHOWN ON PLAN ARE APPROXIMATE AND THE CONTRACTOR IS RESPONSIBLE FOR THE COST RELATED TO CHANGES TO THE SWPP AT NO ADDITIONAL COST TO THE OWNER IF ANY OF THESE AREAS ARE EXCEEDED.
- 13. THE CONTRACTOR IS RESPONSIBLE TO ENSURE ALL AREAS OF SOIL DISTURBANCE ARE STABILIZED DURING CONSTRUCTION AND WHENEVER WORK IS SUSPENDED ON THE PROJECT. CONTRACTOR SHALL SEED AND MULCH THESE AREAS AS REQUESTED BY THE OWNER'S REPRESENTATIVE AT NO ADDITIONAL COST TO THE OWNER.
- 14. CONTRACTOR SHALL NOT WASH CONCRETE TRUCKS ONTO THE BARE GROUND, DIRECTLY INTO STORM OR SANITARY SYSTEMS INCLUDING SWALES, DITCHES OR ADJACENT PROPERTIES. EXCESS CONCRETE AND WASH WATER SHALL BE COLLECTED IN WASH BASIN AND DISPOSED OF PROPERLY.

SILT FENCE SPACING TABLE						
SLOPE	s	OIL TYPE				
SLOPE	SILTY	CLAYS	SANDY			
1:1	50 FT	75 FT	100 FT			
2:1	75 FT	100 FT	125 FT			
4:1	100 FT	125 FT	150 FT			
10:1 OR FLATTER	125 FT	150 FT	200 FT			

	Eng check	S. Phi	llips	
	Coordination			
	Approved			
	Rev		Security	
С	-5			

Priest Lake Water Management Project Outlet Dam Improvements

TEMPORARY EROSION & SEDIMENT CONTROL DETAILS



WORK LIST

SCOUR COUNTERMEASURES

- 1. FILL SCOURED AREAS ALONG THE DOWNSTREAM EDGE OF THE EXISTING APRON WITH EXCESS STREAMBED MATERIAL OR CLEAN FILL
- REMOVE EXISTING ARMOR STONE DOWNSTREAM OF EXISTING 2. CONCRETE APRON. PROVIDE NEW ARMOR STONE DOWNSTREAM OF NEW APRON
- PREPARE SUBGRADE BENEATH APRON EXTENSION, KEYWAY, 3. AND ARMOR STONE.

CONCRETE ELEMENTS

- 1. REFACE THE EDGE OF PIER 6.
- 2. INSTALL NEW APRON EXTENSION WITH KEYWAY AND UPSTAND.
- REPAIR EXISTING UPSTREAM AND DOWNSTREAM WING WALL 3. EXPANSION JOINTS.

TAINTER GATE SYSTEM

- INSTALL NEW TAINTER GATE EXTENSION AT ALL 11 EXISTING 1. TAINTER GATES.
- 2. INSTALL REINFORCING RIBS ON LOWER SECTION OF SKIN PLATE AT ALL 11 EXISTING TAINTER GATES.
- 3. REPLACE BOTH TRUNNION PINS AT ALL 11 EXISTING TAINTER GATES
- REPLACE EXISTING J SEALS ON BOTH SIDES OF ALL 11 EXISTING TAINTER GATES WITH EXTENSION TO ACCOMMODATE GATE EXTENSION.
- REMOVE AND REPLACE EXISTING TRUNNION PIN GREASE 5. FITTINGS WITH LONGER FITTINGS.

MISCELLANEOUS ELEMENTS

REPLACE DAMAGED PORTION OF HANDRAIL INSTALL VIBRATING PIEZOMETERS AT 3 LOCATIONS W/ 2 CONTROL PANEL ON N. ABUTMENT.

NOTES


Μ

MOTT

MACDONALD

Μ


- SHEET PILE WALL IS SHOWN PER 1978 DESIGN DRAWINGS
- 2. DOWNSTREAM ARMOR STONE AND BEDDING STONE UNDER LAYER LIMITS ARE SHOWN PER TECHNICAL SECTION DESIGN DRAWINGS
- 3. SLOPE OF ARMOR STONE SURFACE VARIES TO MEET EXISTING.
- THE LIMITS OF ORIGINAL ARMOR STONE SHOWN IN SECTION A EXTEND ACROSS THE ENTIRE WIDTH OF THE DAM ALONG THE DOWNSTREAM EDGE. LIMITS IN THE SECTION ARE BASED ON 1978 DESIGN DRAWINGS AND SITE CONDITIONS OBSERVED IN THE FIELD.
- 5 DUE TO THE EXISTING STREAM BED MATERIALS. COMPACTED NATURE OF THE NATURAL SUBGRADE SOILS, AND DISPLACEMENT EFFECTS OF RIVER FLOW THE CONTRACTOR CAN ANTICIPATE ENCOUNTERING ARMOR STONE, COBBLES, BOULDERS, AND OTHER OBSTRUCTIONS IN THE RIVERBED AND BANKS OF THE PROPOSED CONSTRUCTION ZONE. THE COST TO REMOVE, DISPOSE OF, STORE OR REINSTATE THE ARMOR STONE, COBBLES, BOULDERS, AND OTHER OBSTRUCTIONS TO FACILITATE CONSTRUCTION SHALL BE INCLUDED IN THE CONTRACTORS BID.
- THE LIMITS OF DISPLACED ARMOR STONE SHOWN ARE 6 APPROXIMATE. ACTUAL WIDTHS AND DEPTHS MAY VARY, CONTRACTOR SHALL VERIFY THE CONDITIONS IN THE FIELD
- VWP SHALL BE EQUIVALENT TO DURHAM GEO SLOPE INDICATOR PART NUMBER 52611625, LOW-PRESSURE VWP (25PSI) WITH CABLING PART NUMBER 50613824, LENGTH DETERMINED BY CONTRACTOR.
- VWP SHALL BE LOCATED IN A BOREHOLE EMBEDDED BETWEEN 10 AND 15 FEET BELOW THE APRON AT CONTRACTOR DISCRETION, BUT ITS ELEVATION SHALL BE MEASURED TO BE ACCURATE TO WITHIN 2 INCHES
- CONTRACTOR TO PROVIDE AS-BUILT DRAWING OR MARKUP IDENTIFYING ELEVATION OF VWP, CONDUIT RUNS, AND VWP LABELING AT VWP CONTROL PANEL.





W mottmac.com


1601 5th Avenue

Suite 800









SP

SK

Ch'k'd App'd

Project Number

376997

B/O

17

Fota

25

TM 90% SUBMITTAL

Drawn Description

0 5/6/20

Rev Date


king\hmm\ports_harbors\tad69807\dms25901\376997	 Priest Lake Dam - Handrail Replacement Details.dwg Jun 12, 2020 - 5:27PM Tadlock, Brice

W mottmac.com

C:\pwwor

	Eng check	S. Phillips	Priest Lake Water
	Coordination		Management Project
	Approved		Outlet Dam Improvements
	Rev	Security	
			MISCELLANEOUS STEEL DETAILS
S	-6		

Drawing Number



18

376997


Ch'k'd App'd

Rev Date

Drawn Description

25

	Eng check	S. Phi	llips		Tite Priest Lake Water					
	Coordination	ו			Management Project					
	Approved				Outlet Dam Improvements					
	Rev		Security							
					SUBSTRUCTURE PLAN					
A	-1									




CONTRACTOR SHALL RELOCATE AND RESET MATERIAL TO FILL DEEPER VOIDS BELOW THE TOP OF BEDDING LINE OR SCOUR HOLES AS DIRECTED BY OWNER'S REPRESENTATIVE. SUITABILITY OF MATERIAL RE-USE SHALL BE DETERMINED BY OWNER'S REPRESENTATIVE. IF OWNER'S REPRESENTATIVE DETERMINES MATERIAL IS UNSUITABLE FOR RE-USE CONTRACTOR SHALL DISPOSE OF MATERIAL AT NO ADDITIONAL COST TO THE OWNER. SEE SPECIFICATION SECTION

PLACE BEDDING STONE DIRECTLY BENEATH APRON EXTENSION AND ARMOR ROCK TO LIMITS IDENTIFIED ON PLAN AND IN SECTION. AGGREGATES USED SHALL BE FREE OF ADHERENT COATINGS AND DELETERIOUS MATERIALS SUCH AS ORGANICS OR CONSTRUCTION MATERIALS. BEDDING STONE MATERIAL AND GRADATION SHALL MEET THE REQUIREMENTS LISTED IN

PLACE ARMOR STONE ON BEDDING STONE TO TOP OF PROPOSED CONCRETE UPSTAND FOR LIMITS IDENTIFIED. ARMOR STONE MATERIAL AND GRADATION SHALL MEET THE REQUIREMENTS

	Eng check	L. Gre	eno		Priest Lake Water			
	Coordination	ordination P. Kobialka			Management Project			
	Approved	S. Phillips			Outlet Dam Improvements			
	Rev		Security					
					APRON EXTENSION SECTIONS			
A	-2							



Project Number

376997

B/O

20

Fota

25

Drawing Number

SK SP

Ch'k'd App'd

monte	harbore\tad60807\dme25001\376007	Priest Lake Dam - Apro	n Reinforcing Plan du	a lun 12	2020 - 5:28 DM Tadlock I	Brice


W mottmac.com

Rev Date Drawn Description

0 5/6/20


TM 90% SUBMITTAL


	Eng check	L. Gre	Greno		Title Priest Lake Water
	Coordination	P. Ko	P. Kobialka		Management Project
	Approved	S. Phi	S. Phillips		Outlet Dam Improvements
	Rev		Security		
					APRON REINFORCING PLAN
A	-3				



Priest Lake Dam - Apron Reinforcing Plan.dwg Jun 12, 2020 - 5:28PM

	Eng check	L. Greno			Tite Priest Lake Water
	Coordination	P. Kobialka			Management Project
	Approved	S. Phi	illips		Outlet Dam Improvements
	Rev		Security		
					APRON WALL ELEVATIONS
A-4					






REINF.	
URING	

- REMOVAL OF STRUCTURAL CONCRETE SHALL BE A MINIMUM OF 4" OR TO SOUND CONCRETE, IF POOR CONDITION CONCRETE EXTENDS BEYOND THE 6" REMOVAL LIMIT, THE CONTRACTOR SHALL NOTIFY THE OWNER'S REPRESENTATIVE BEFORE REMOVING ADDITIONAL CONCRETE TO REACH SOUND CONCRETE.
- 2. CONTRACTOR TO MAINTAIN AND PROTECT EXISTING REINFORCEMENT.
- SAW CUT HORIZONTALLY THE EXISTING WALL AS DIMENSIONED ON THE EXISTING ELEVATION THIS SHEET. SAW CUT LINE SHALL BE CUT LEVEL AND PARALLEL WITH EXISTING PIER PROFILE.
- 4. REMOVE THE LOOSE AND UNSOUND CONCRETE ON THE PIER FACE WITHIN THE LIMITS IDENTIFIED IN ELEVATION.
- 5. MECHANICALLY PREPARE CONCRETE SURFACE TO ENSURE BONDING OF REPAIR MATERIAL.
- PREPARE AND APPLY BONDING AGENT TO ROUGHENED CONCRETE SURFACE WITHIN LIMITS OF PARTIAL DEPTH REPAIR IDENTIFIED ON WALL ELEVATIONS IN ACCORDANCE WITH THE BONDING AGENTS MANUFACTURER RECOMMENDED SPECIFICATIONS.
- 7. FORM AND POUR REPAIR CONCRETE WITHIN THE LIMITS OF THE PARTIAL DEPTH REPAIR IDENTIFIED IN ELEVATION.

	Eng check	L. Greno			Title Priest Lake Water
	Coordination	P. Kobialka			Management Project
	Approved	S. Phi	illips		Outlet Dam Improvements
	Rev		Security		
					PIER 6 REPAIR DETAILS
P	-1				



Project Number

376997

B/C

24

ota

25

SP

SK

Ch'k'd App'd

TM 90% SUBMITTAL

Drawn Description

0


Rev Date

5/6/20

ous Details.dwg Jun 12, 2020

Drawing Number

	Eng check	S. Phillips		Priest Lake Water
	Coordination			Management Project
	Approved			Outlet Dam Improvements
	Rev Security		I	MISCELLANEOUS DETAILS 1
М	-1			



- --- - - -

	Eng check	S. Phillips		Priest Lake Water
	Coordination			Management Project
	Approved	proved		Outlet Dam Improvements
	Rev	Security		
				MISCELLANEOUS DETAILS 2
М	-2			